



Project Description

The original asphalt pavement constructed in the early 1980s had served its useful life and was in need of replacement. Becher Hoppe worked with the Prentice Municipal Airport to reconstruct Runway 9-27.

Project Features

- Pulverized pavement and base course, recompact and paved with 3 inches of new asphalt pavement
- Reconstructed Runway 9-27, taxiway, and apron
- Expanded aircraft tie down aprons
- New turnarounds on runway ends
- Land acquisition for airspace protection
- Tree clearing

Firm's Involvement

- Scoped project
- Surveyed
- Performed obstruction analysis
- Designed pavement
- Prepared cost estimates and construction documents
- Provided construction engineering services